

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
04 . Preliminary & Misc. Work					
04-490	Jafry bamboo fencing with bamboo post : 75mm x 75mm gap				
30.	<u>Wood Work</u>				
	30-010 Bamboo, Barrack : 6m long, 60-80mm dia..	0.1852	No.	@ Tk. . . .per	100 No. Tk.
	30-040 Bamboo, Makla : 6m long, 60-80mm dia....	0.6210	No.	@ Tk. . . .per	100 No. Tk.
				Sub Total	Tk.
40.	<u>Metal Work</u>				
	40-770 Wire, G.I. 20/22 BWG	0.0275	kg	@ Tk. . . .per	kg Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-370 Labour, Skilled	0.0512	day	@ Tk. . . .per	day Tk.
	80-375 Labour, Unskilled	0.0387	day	@ Tk. . . .per	day Tk.
	80-375 (Labour, Unskilled)	0.0003	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.