

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
04 . Preliminary & Misc. Work					
04-500	Bamboo fencing around water level gauge : 1.0m x 1.0m				
30.	<u>Wood Work</u>				
	30-030 Bamboo, Barrack : 7.5m long, > 100mm dia	1.4000	No.	@ Tk. . . .per	100 No. Tk.
	30-040 Bamboo, Makla : 6m long, 60-80mm dia....	3.0290	No.	@ Tk. . . .per	100 No. Tk.
				Sub Total	Tk.
40.	<u>Metal Work</u>				
	40-310 Nails; 37mm to 125mm	3.0290	kg	@ Tk. . . .per	kg Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-370 Labour, Skilled	0.1000	day	@ Tk. . . .per	day Tk.
	80-375 Labour, Unskilled	0.1250	day	@ Tk. . . .per	day Tk.
	80-375 (Labour, Unskilled)	0.0012	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.