

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
16. Earthwork					
16-350-10	Earth work by carried earth(manual compaction):300m to 1.0km				
20.	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.1070	ltr	@ Tk. . . .per	ltr Tk.
	20-310 Lubricant (Mobile oil etc.)	0.0054	ltr	@ Tk. . . .per	ltr Tk.
	20-560 Royalty of earth	1.0000	cum	@ Tk. . . .per	cum Tk.
				Sub Total	Tk.
70.	<u>Equipment, Tools</u>				
	70-060 Cargo Truck (without Fuel & Lubricant)..	0.0213	day	@ Tk. . . .per	day Tk.
	70-255 Iron Rammer, 7.0 kg	0.0800	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-305 Head Man	0.0022	day	@ Tk. . . .per	day Tk.
	80-375 Labour, Unskilled	0.5213	day	@ Tk. . . .per	day Tk.
	80-375 (Labour, Unskilled)	0.0052	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.