

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
56 . Road Construction					
56-430	Filling expansion joints with asphalt, sand and jute waste..				
10.	<u>Materials : Concrete</u>				
	10-380 Sand, FM >= 1.5	0.0070	cum	@ Tk. . . .per cum	Tk.
				Sub Total	Tk.
20.	<u>Materials : Misc.</u>				
	20-125 Bitumen : 80/100	0.6000	kg	@ Tk. . . .per kg	Tk.
	20-535 Rope : Jute String	0.0547	kg	@ Tk. . . .per kg	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.2461	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.