

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
60 . Drain Construction					
60-300-50	Laying in position, R.C.C pipe : 1050mm dia				
80.	<u>Labour</u>				
80-370	Labour, Skilled	0.0840	day	@ Tk. . . .per day	Tk.
80-375	Labour, Unskilled	0.0840	day	@ Tk. . . .per day	Tk.
80-375	(Labour, Unskilled)	0.0008	day	@ Tk. . . .per day	Tk. (Misc. Sundry)
80-425	Mason	0.0416	day	@ Tk. . . .per day	Tk.
80-430	Mason, Head	0.0203	day	@ Tk. . . .per day	Tk.
Sub Total					Tk.
Sum of Sub Total					Tk.
Overhead &					2.5 Tk.
Item Total					Tk.
Contractor's					10 % Tk.
Total					Tk.
VAT					5.5 % Tk.
Item Grand Total					Tk.