

## ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
<b>64. Building Construction</b>					
<b>64-460</b>	Partex board in ceiling : Aluminium frame : 600mmx600mm grid				
30.	<u>Wood Work</u>				
	30-105 Board, Partex : 12mm thick. ....	1.0000	sqm	@ Tk. . . .per	sqm Tk. ....
				<b>Sub Total</b>	Tk. ....
40.	<u>Metal Work</u>				
	40-585 Screw, 25mm ... ..	0.3333	dzn	@ Tk. . . .per	dzn Tk. ....
	40-610 Rowel plug. ....	0.3333	dzn	@ Tk. . . .per	dzn Tk. ....
	40-685 Aluminium Tee. ....	2.6667	m	@ Tk. . . .per	m Tk. ....
	40-690 Aluminium Angle ... ..	1.3334	m	@ Tk. . . .per	m Tk. ....
	40-755 Wire, G.I, 12 BWG ... ..	0.1104	kg	@ Tk. . . .per	kg Tk. ....
				<b>Sub Total</b>	Tk. ....
80.	<u>Labour</u>				
	80-080 Carpenter ... ..	0.2000	day	@ Tk. . . .per	day Tk. ....
	80-085 Carpenter, Head ... ..	0.0500	day	@ Tk. . . .per	day Tk. ....
	80-090 Carpenter, Helper ... ..	0.2500	day	@ Tk. . . .per	day Tk. ....
	80-375 Labour, Unskilled ... ..	0.3300	day	@ Tk. . . .per	day Tk. ....
	80-375 (Labour, Unskilled ... ..)	0.0033	day	@ Tk. . . .per	day Tk. .... (Misc. Sundry)
				<b>Sub Total</b>	Tk. ....
				<b>Sum of Sub Total</b>	Tk. ....
				<b>Overhead &amp;</b>	2.5 Tk. ....
				<b>Item Total</b>	Tk. ....
				<b>Contractor's</b>	10 % Tk. ....
				<b>Total</b>	Tk. ....
				<b>VAT</b>	5.5 % Tk. ....
				<b>Item Grand Total</b>	Tk. ....