

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
84. Electrical Work					
84-100-40	Distribution wiring(surface) : call bell point(Eastern)				
40.	<u>Metal Work</u>				
	40-320 Nails; 13mm to 20mm	0.0500	kg	@ Tk. . . .per	kg Tk.
	40-585 Screw, 25mm	1.5000	dzn	@ Tk. . . .per	dzn Tk.
				Sub Total	Tk.
60.	<u>Electrical Work</u>				
	60-016 Batten, Teak Wood, 13 mm x 13 mm	7.5000	m	@ Tk. . . .per	100 m Tk.
	60-148 Calling Bell Push Button Switch	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-160 Ceiling Rose	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-231 Clip, Link,(with single eye)	4.5000	dzn	@ Tk. . . .per	dzn Tk.
	60-470 Round Block	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-480 Rowel Plug	1.5000	dzn	@ Tk. . . .per	dzn Tk.
	60-850 Wire,PVC;2C;1.5mm ² ;	8.0000	m	@ Tk. . . .per	100 m Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-190 Electrician	0.2000	day	@ Tk. . . .per	day Tk.
	80-200 Electrician, Helper	0.2000	day	@ Tk. . . .per	day Tk.
	80-200 (Electrician, Helper)	0.0020	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.