

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
84. Electrical Work					
84-440-20	Supply & fix batten light in ceiling : 200mm dia globe				
40.	<u>Metal Work</u>				
	40-585 Screw, 25mm	0.1666	dzn	@ Tk. . . .per	dzn Tk.
				Sub Total	Tk.
60.	<u>Electrical Work</u>				
	60-058 Board, Wood, 80 mm round	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-129 Bulb, 15 - 60 W, Pin type	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-400 Holder, Batten	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-480 Rowel Plug	0.1666	dzn	@ Tk. . . .per	dzn Tk.
	60-505 Shade, Globe, 200 mm	1.0000	No.	@ Tk. . . .per	No. Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-190 Electrician	0.0600	day	@ Tk. . . .per	day Tk.
	80-200 Electrician, Helper	0.0600	day	@ Tk. . . .per	day Tk.
	80-200 (Electrician, Helper)	0.0002	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.