

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
24. Plastering Work					
24-160-20	Minimum 6mm thick plaster over concrete surface : (1:4)				
10.	<u>Materials : Concrete</u>				
	10-100 Cement : Portland	3.0000	kg	@ Tk. . . .per	kg Tk.
	10-375 Sand, FM >= 1.3	0.0076	cum	@ Tk. . . .per	cum Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.2421	day	@ Tk. . . .per	day Tk.
	80-375 (Labour, Unskilled)	0.0070	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
	80-425 Mason	0.1076	day	@ Tk. . . .per	day Tk.
	80-430 Mason, Head	0.0090	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.