

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
24. Plastering Work					
24-300-10	Rule pointing to brick work with (1:2) sand cement mortar...				
10.	<u>Materials : Concrete</u>				
	10-100 Cement : Portland	2.0000	kg	@ Tk. . . .per	kg Tk.
	10-375 Sand, FM >= 1.3	0.0030	cum	@ Tk. . . .per	cum Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.1614	day	@ Tk. . . .per	day Tk.
	80-375 (Labour, Unskilled)	0.0048	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
	80-425 Mason	0.1345	day	@ Tk. . . .per	day Tk.
	80-430 Mason, Head	0.0067	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.