

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-250-40	Brick work (1:4) in brick block : 50cmx50cmx30cm				
10.	<u>Materials : Concrete</u>				
	10-040 Bricks : 1st Class	31.2270	No.	@ Tk. . . .per 1000 No.	Tk.
	10-100 Cement : Portland ...	7.5000	kg	@ Tk. . . .per kg	Tk.
	10-380 Sand, FM >= 1.5	0.0206	cum	@ Tk. . . .per cum	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.0553	day	@ Tk. . . .per day	Tk.
	80-425 Mason	0.0536	day	@ Tk. . . .per day	Tk.
	80-430 Mason, Head	0.0016	day	@ Tk. . . .per day	Tk.
	80-435 Mason, Helper	0.0265	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & 2.5	Tk.
				Item Total	Tk.
				Contractor's 10 %	Tk.
				Total	Tk.
				VAT 5.5 %	Tk.
				Item Grand Total	Tk.