

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
56 . Road Construction					
56-130	Brick on edge soling in Herring Bone Bond (HBB) :				
10.	<u>Materials : Concrete</u>				
	10-040 Bricks : 1st Class	52.7240	No.	@ Tk. . . .per 1000 No.	Tk.
	10-360 Sand, FM >= 0.5	0.0305	cum	@ Tk. . . .per cum	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.1076	day	@ Tk. . . .per day	Tk.
	80-425 Mason	0.0403	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & 2.5	Tk.
				Item Total	Tk.
				Contractor's 10 %	Tk.
				Total	Tk.
				VAT 5.5 %	Tk.
				Item Grand Total	Tk.