

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
56 . Road Construction					
56-230	Construction of compacted water bound macadam base course ..				
10.	<u>Materials : Concrete</u>				
	10-040 Bricks : 1st Class	381.3480	No.	@ Tk. . . .per 1000 No.	Tk.
				Sub Total	Tk.
70.	<u>Equipment, Tools</u>				
	70-345 Road Roller : 8 hrs day (with fuel etc.)	0.0141	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-370 Labour, Skilled	0.0141	day	@ Tk. . . .per day	Tk.
	80-375 Labour, Unskilled	3.1779	day	@ Tk. . . .per day	Tk.
	80-375 (Labour, Unskilled)	0.0794	day	@ Tk. . . .per day	Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & 2.5	Tk.
				Item Total	Tk.
				Contractor's 10 %	Tk.
				Total	Tk.
				VAT 5.5 %	Tk.
				Item Grand Total	Tk.