

## ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
<b>56. Road Construction</b>					
<b>56-310</b>	9mm thick pre-mixed bitumenous seal coat with pea gravels:..				
10.	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8 ... ..	0.0100	cum	@ Tk. . . .per	cum Tk. ....
	10-495 Stone, Pea Gravel : 6mm down graded ....	0.0150	cum	@ Tk. . . .per	cum Tk. ....
				<b>Sub Total</b>	Tk. ....
20.	<u>Materials : Misc.</u>				
	20-125 Bitumen : 80/100 ... ..	1.2000	kg	@ Tk. . . .per	kg Tk. ....
				<b>Sub Total</b>	Tk. ....
30.	<u>Wood Work</u>				
	30-425 Wood, Fire ... ..	0.8880	kg	@ Tk. . . .per	kg Tk. ....
				<b>Sub Total</b>	Tk. ....
70.	<u>Equipment, Tools</u>				
	70-345 Road Roller : 8 hrs day (with fuel etc.)	0.0007	day	@ Tk. . . .per	day Tk. ....
				<b>Sub Total</b>	Tk. ....
80.	<u>Labour</u>				
	80-305 Head Man .. ..	0.0022	day	@ Tk. . . .per	day Tk. ....
	80-370 Labour, Skilled ... ..	0.0215	day	@ Tk. . . .per	day Tk. ....
	80-375 Labour, Unskilled ... ..	0.0430	day	@ Tk. . . .per	day Tk. ....
				<b>Sub Total</b>	Tk. ....
				<b>Sum of Sub Total</b>	Tk. ....
				<b>Overhead &amp;</b>	2.5 Tk. ....
				<b>Item Total</b>	Tk. ....
				<b>Contractor's</b>	10 % Tk. ....
				<b>Total</b>	Tk. ....
				<b>VAT</b>	5.5 % Tk. ....
				<b>Item Grand Total</b>	Tk. ....