

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
64. Building Construction					
64-210-10	3mm thick red oxide flooring : (1:3)				
10.	<u>Materials : Concrete</u>				
	10-100 Cement : Portland	5.1500	kg	@ Tk. . . .per kg	Tk.
				Sub Total	Tk.
20.	<u>Materials : Misc.</u>				
	20-420 Paint : Red Oxide	1.4292	kg	@ Tk. . . .per kg	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.1076	day	@ Tk. . . .per day	Tk.
	80-375 (Labour, Unskilled)	0.0011	day	@ Tk. . . .per day	Tk. (Misc. Sundry)
	80-425 Mason	0.0538	day	@ Tk. . . .per day	Tk.
	80-430 Mason, Head	0.0753	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.