

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
80 . Plumbing Work					
80-780-20	Supply & fitting squatting/flat urinals : coloured				
10.	<u>Materials : Concrete</u>				
	10-100 Cement : Portland	0.0100	kg	@ Tk. . . .per	kg Tk.
	10-375 Sand, FM >= 1.3	0.0200	cum	@ Tk. . . .per	cum Tk.
				Sub Total	Tk.
50.	<u>Plumbing Work</u>				
	50-076 Cistern, High Level, C.I.	1.0000	No.	@ Tk. . . .per	No. Tk.
	50-167 Cock, Stop, C.P., 13mm dia	1.0000	No.	@ Tk. . . .per	No. Tk.
	50-440 Pipe, PVC., 32mm dia	2.2500	m	@ Tk. . . .per	m Tk.
	50-855 Urinal, Indian; Coloured.	1.0000	No.	@ Tk. . . .per	No. Tk.
	50-859 Valve, Check, Brass, 13mm dia	1.0000	No.	@ Tk. . . .per	No. Tk.
	50-936 Wash Basin, Coupling, P.V.C., 13 mm dia.	1.0000	No.	@ Tk. . . .per	No. Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-370 Labour, Skilled	1.0000	day	@ Tk. . . .per	day Tk.
	80-560 Plumber	1.0000	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.