

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
84. Electrical Work					
84-120-30	Concealed distribution wiring : 5amps socket (Eastern)				
40.	<u>Metal Work</u>				
	40-580 Screw, 19mm	0.3330	dzn	@ Tk. . . .per	dzn Tk.
				Sub Total	Tk.
60.	<u>Electrical Work</u>				
	60-608 Socket, 2 Pin, 5 A	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-740 Switch, Tumbler, 5 A	1.0000	No.	@ Tk. . . .per	No. Tk.
	60-832 Wire, Copper, SWG, No. 16	0.0030	kg	@ Tk. . . .per	kg Tk.
	60-880 Wire,PVC;	0.6100	m	@ Tk. . . .per	100 m Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-190 Electrician	0.0130	day	@ Tk. . . .per	day Tk.
	80-200 Electrician, Helper	0.0130	day	@ Tk. . . .per	day Tk.
	80-200 (Electrician, Helper)	0.0001	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.